



COOCHBEHAR REGIONAL OFFICE  
Dinhata Road, Morapora Chowpathi  
P.O. & Dist : Coochbehar, 736101  
Mail: rocooc@rrubkgh.in

Date: 30/07/2025

## NOTICE FOR SEEKING QUOTATION

Notice inviting quotation for electrical works of our Baxirhat Branch (400005) located at Postoffice para, P.O. & P.S. Baxirhat, Tufanganj II, Dist. Coochbehar, Pincode-736131.

Interested vendors are requested to submit sealed quotations for the said works to our Regional Office in person on any working day during working hours (10 am to 5 pm) on or before 20/08/2025. Quotations will be opened at Regional Office on 21/08/2025 at 12:30 pm in presence of shortlisted vendors.

Details of work are attached below.


### Terms & Conditions:

1. Quotation will be considered on lower rate (LI) basis.
2. After expiry of scheduled time frame no quotation will be accepted.
3. Bank authority reserves the right to accept or cancel bid unilaterally without assigning any reason thereof prior to the placement or supply order/signing contract thereby.
4. Delay or deviation in work material or time may attract penalty on bill amount.
5. GST no. is mandatory to submit quotation.
6. Rates will be inclusive all charges except GST.
7. Tenderers are advised to visit the branch site to assess the scope of work.
8. Uncompromising adherence to material and workmanship quality standards is required.
9. Vendors should preferably have an established office unit in North Bengal.

Regional Manager

For and on behalf of  
WEST BENGAL GRAMIN BANK

Regional Manager  
Regional Office, Cooch Behar  
West Bengal Gramin Bank  
Coochbehar Region



Satyam Kumar  
Manager, RO Coochbehar  
Emp ID - 24550

For and on behalf of  
WEST BENGAL GRAMIN BANK  
Regional Manager  
Regional Office, Cooch Behar





COOCHBEHAR REGIONAL OFFICE  
Dinhata Road, Morapora Chowpathi  
P.O. & Dist : Coochbehar, 736101  
Mail: rocooc@rrubkbg.in

## QUOTATION

To,  
The Regional Manager  
West Bengal Gramin Bank  
Coochbehar Region  
Dinhata Road, Coochbehar

### Electrical Work Of WBGB Baxirhat Branch, Coochbehar

SLNo.	Description	Quantity/area	Rate	Amount
1.	Supply and laying of CAT-6 Cable through suitable size PVC casing from server to HUB, HUB to Computer Data socket including interconnection mending good etc as required make Havells/Finolex/Polycab/KEI	80 mtr		
2.	Supply and fixing on wall/furniture/partition recessed non modular type computer data socket D-Link make with mounting box and front plate complete with mending good etc as required make L&T/Anchor-Panasonic/Crabtree/Legrand	8 nos.		
3.	Supply and laying 2x6 sqmm + 1x2.5 sqmm copper wire from panel to CDB Havells/Finolex/Polycab/KEI	30 mtr		
4.	Supply and laying 2x2.5 mm + 1x1.5 sqmm copper wire MCB DB to power plug Havells/Finolex/Polycab/KEI	70 mtr		
5.	Supply and fixing and connection of UPS circuit line with 1.1 kv grade PVC insulated non sheathed stranded copper cable with 2x2.5 sqmm + 1X1.5 mm throughout rigid PVC conduit 20 mm 1.6 mm wall thickness, with ISI mark to lay from UPS MCB DB to plug point board Havells/Finolex/Polycab/KEI	80 mtr		
6.	Supply and fabricating and fixing of computer board made of 2 nos. 5 pin 6Amp modular socket and 1 no 5 pin 16Amp socket along with 6A and 16Amp individual switch having fixed with 1 no LED indicator board fuse on suitable size GI switch board connection & recessed in wall with mending good all damages L&T/Anchor/Crabtree/Legrand	8 nos.		
7.	Supply, installation, testing and commissioning of legrand make 32Amp 3pin wall mounted industrial type metal clad socket with plug top & 32 Amp SPN MCB contro; for UPS Room L&T/Anchor/Crabtree/Legrand	2 mtr		
8.	Supply laying and connection of UPS incoming power line with 2x6 sqmm + 1x2.5 sqmm PVC insulated stranded copper wire from panel board to UPS incoming power switch Hvells/Finolex/Polycab/KEI	45 mtr		





COOCHBEHAR REGIONAL OFFICE  
Dinhata Road, Morapora Chowpathi  
P.O. & Dist : Coochbehar, 736101  
Mail: rocooc@rrubkgb.in

9.	Earthing with copper plate 610x610x3 mm size having weight of 9.84 kg and 1 no. 25x5 mm copper strip 3.20 mt long and 1 no 6 sqmm PVC insulated stranded copper wire 4 mtr long incl. S&F 15 mm dia GI pipe ISI medium protection 4 mtr long to be ground level to an average depth of 3.65 mtr below the ground level and restoring the surface duly rammed incl. providing 3.0 mt long 25 mm dia GI pipe for periodic for UPS	1 set		
10.	Providing and GI wire gauge in grown from earth pit to earthing station & finally connected to main panel & meter box	25 mtr		
11.	Providing and fixing pipe Earthing 1S3043 Code 3.0 mm deep with 40 mm dia GI pipe with perforation filled with alternate layers of charcoal and salt. The item includes funnel on top in brick masonry chamber with CI cover for watering purpose	2 set		
12.	Main Electrical cubical panel : 500 V 100 Amp TPN HRC FUSE-1 500 V 63 Amp TPN HRC FUSE-1 500 V 63 Amp TPN on load change over switch-1 500 Amp 100 Amp busbar Cu with BBC on heavy duty porcelain chairs 2 set 500 V 63 Amp FB MCB 2 no 230 v/415 40A 10KA SP MCB-4 no 230 V/415 25 A SP MCB-1 And Havells xpro glow sign board 100 Amp Ammeter with selector sitch 1 set 100/5ct-3nos LED indicator lamp 3 no	1 no.		
13.	Main incoming fuse unit supply fixing of Amp TPN HRC type SFU at WBSEB end for main incoming on MS angal frame and 2 nos cable box including connection	1 no.		
14.	Supply & installation of following Havells/Legrand make 10 way TPN MCB distribution board with MCB having short circuit breaking capacity 10 ka or RCBO of 100 Amp sensity having overload short circuit & earth leakage protection complete with neutral phase & earth bar with 1 no 40A dp rcbo as incoming 8x6Amp SPMCB as outgoing to be partially recessed in wall	1 set		
15.	Dismantling and refixing of CAT-6, 24 port patch panel	1 nos.		
16.	Supply of CAT-VI 1 mtr. Patch cord	8 nos.		
17.	Supply of CAT-VI 2 mtr. Patch cord	8 nos.		
18.	Dismantling and refixing of 9U-rack	1 no.		
19.	Lighting cutoof 32 Amp DP MCB with boc complete Legrand	1 no.		
20.	UPS Main supply & installation of 63Amp 2 pole MCB with suitable size metal enclosure for UPS MAIN	1 set		



COOCHBEHAR REGIONAL OFFICE  
Dinhata Road, Morapora Chowpathi  
P.O. & Dist : Coochbehar, 736101  
Mail: rocooc@rrubkgb.in

	CONTROL NEAR ups			
21.	Dismatling and refixing of CCTV	1 no.		
22.	Supply and laying of cable	70 mtr		
23.	BNC socket	8 sets		
24.	Dismantling and reinstallation of UPS battery	1 set		
25.	Supply and fitting 36 W LED 2X2 SQUARE LIGHT OR SIMILAR APPROVED OF Havells/Crompton/ ISI mark (high efficiency surface mounted LED luminire)	10 nos.		
26.	Supply and fitting 12 W LED 150 mm dia round down light approved of Havells/Crompton/ ISI Mark	6 nos.		
27.	AC POINT :- Supply and Installation of 2.5mm + 0.75mm running earth, Pvc Catching, 20Amp Stator and 20Amp Socket including all. (all new item are – Havells,Anchor,Finolex,ISI mark company)	3 nos.		

Total Amount (Inclusive all charges & With Out GST) =

GST No:

Signature with Seal.